



P.O. Box "J"  
MANSON, WASHINGTON 98831  
PHONE: (509) 687-3548  
STAFF@LCRD.ORG

SERVICE ID: \_\_\_\_\_

**APPLICATION FOR DOMESTIC WATER HOOK-UP**

NAME: \_\_\_\_\_

PARCEL#: \_\_\_\_\_

MAILING ADDRESS: \_\_\_\_\_

**TYPE OF SERVICE:**

PHONE NUMBER: \_\_\_\_\_

E-MAIL: \_\_\_\_\_

REQUESTED METER SIZE \_\_\_\_\_

PROPERTY ADDRESS: \_\_\_\_\_

- SINGLE FAMILY RESIDENCE
- ACCESSORY DWELLING UNIT (ADU)
- COMMERCIAL BUILDING
- DUPLEX/TRIPLEX/MULTI FAMILY
- OTHER: \_\_\_\_\_

**WHAT DATE WOULD YOU LIKE THE METER SERVICE INSTALLED BY?** \_\_\_\_\_

\* IF A METER BOX IS NOT ALREADY PRESENT, PLEASE USE A STAKE LABELED "WATER" TO MARK YOUR DESIRED LOCATION AND ATTACH A PARCEL MAP TO THIS FORM SHOWING ITS LOCATION. LCRD REQUIRES **30 DAYS ADVANCE NOTICE** PRIOR TO SERVICE INSTALLATION.

**CUSTOMER ACKNOWLEDGES AND AGREES TO THE FOLLOWING BY SIGNING THIS DOCUMENT:**

1. THE CUSTOMER WILL HAVE THE BACKFLOW PREVENTION ASSEMBLY (DCVA) INSPECTED AND TESTED ANNUALLY AT YOUR OWN COST AS REQUIRED BY THE DEPARTMENT OF HEALTH WAC 246-290-490.
2. THE CUSTOMER HAS READ THE BROCHURE ON HOW TO PREVENT THERMAL EXPANSION AND ACKNOWLEDGES THAT LCRD RECOMMENDS THE INSTALLATION OF THERMAL EXPANSION TANK.
3. THE CUSTOMER UNDERSTANDS THAT INSULATING THE METER AND DCVA BOX DURING THE WINTER MONTHS IS YOUR RESPONSIBILITY. LCRD RECOMMENDS PLACING INSULATION IN A GARBAGE BAG, TO KEEP IT FROM GETTING WET, AND PLACING IT BELOW AND ABOVE THE DCVA IN EFFORT TO PREVENT IT FROM FREEZING.
4. HIGH PRESSURE: IN ORDER TO PROVIDE WATER SERVICE TO ALL AREAS OF OUR DISTRICT, SOME SERVICES WILL HAVE HIGH WATER PRESSURE AND WILL NEED TO INSTALL A PRESSURE REDUCING VALVE (PRV) ON THE MAIN WATER LINE.
5. LOW PRESSURE ZONE: LCRD IS REQUIRED TO PROVIDE A MINIMUM OF 30 PSI AT THE METER, WHICH IS LOCATED AT THE EDGE OF YOUR PROPERTY. A PRIVATE BOOSTER PUMP SYSTEM WILL BE NEEDED IF THE PSI AT YOUR HOUSE IS NOT ADEQUATE. YOU ARE RESPONSIBLE FOR PROVIDING POWER FOR THE PRIVATE PUMP AND MAINTAINING IT.

**CUSTOMER SIGNATURE:** \_\_\_\_\_

**DATE:** \_\_\_\_\_

**NOTE:** MONTHLY RATE SERVICE FEES WILL START 60 DAYS AFTER HOOK UP FEES ARE PAID OR 30 DAYS AFTER THE WATER METER IS INSTALLED REGARDLESS OF WHETHER YOU ARE PHYSICALLY USING THE WATER OR NOT. THE HOOK UP FEE WILL INCLUDE THE INSTALLATION OF A METER, DOUBLE CHECK VALVE ASSEMBLY AND A BALL VALVE WHICH IS THE CUSTOMER'S SHUT OFF VALVE.

3/4" HOOK UP FEE (PER ERU)    \$8,000 x \_\_\_\_\_ ERU'S  
 1" HOOK UP FEE (PER ERU)    \$8,750 x \_\_\_\_\_ ERU'S  
 ADU HOOK UP FEE (0.5 ERU)    \$ \_\_\_\_\_  
 TAP FEE    \$1,600 [    ]  
 ROAD CROSSING FEE    \$2,600 [    ]  
 MISC ADDITIONAL FEES    \$ \_\_\_\_\_  
**TOTAL AMOUNT DUE:    \$ \_\_\_\_\_**

CHECK NUMBER: \_\_\_\_\_

DATE PAID: \_\_\_\_\_

RECEIVED BY: \_\_\_\_\_

LAKE CHELAN RECLAMATION DISTRICT

HOOK UP COMPLETED ON: \_\_\_\_\_

HOOK UP BY: \_\_\_\_\_

AMR TRANSMITTER NO: \_\_\_\_\_

BACKFLOW SERIAL: \_\_\_\_\_


METER BODY SERIAL: \_\_\_\_\_

BACKFLOW MAKE/MODEL: WILKINS 350XL

CHLORINE RESIDUAL TEST RESULT: \_\_\_\_\_ MG/L

BACKFLOW SIZE: \_\_\_\_\_

**DEVELOPER/CONTRACTOR INSTALLATION RESPONSIBILITY**



**(DO NOT COVER UNTIL DISTRICT INSPECTS)**

**CUSTOMER INITIAL: \_\_\_\_\_**

**NOTES:**  
 ALL DOMESTIC DEVICES AND FITTINGS MUST BE LEAD FREE.


MATERIAL SUBSTITUTIONS OR DETERMINATION OF EQUAL ARE AT THE SOLE DISCRETION OF LAKE CHELAN RECLAMATION DISTRICT.

SERVICE LINE TO BE 90° OFF MAIN LINE. MAGNETIC TAPE TO BE BURIED OVER SERVICE LINE FOR LOCATION.

**SINGLE 3/4" METER INSTALLATION:**  
 METER - 3/4" x 3/4" Badger Recordall Nutating Disc Flowmeter, L. Bronze External Thread Body, Noryl Chamber, Plastic Thrust Roller, Bronze Bottom, Meter Mounted Low Temp Register, No Connections, NSF 61, Cubic Feet Reader  
 COIL BOX - Mueller No. 250 CS 15 36 LSB5N  
 LID - Mueller No. 203 CS 15 36 FBB5N  
 INSULATION RING - Mueller No. 790022

**DOUBLE 3/4" METER INSTALLATION:**  
 (2) METERS - see single 3/4" meter installation above  
 COIL BOX - Mueller No. 203 CD 18 36 FBB5N  
 LID - Mueller No. 790111  
 INSULATION RING - Mueller No. 790153

**SINGLE 1" METER INSTALLATION:**  
 METER - 1" Badger Recordall Nutating Disc Flowmeter, L. Bronze External Thread Body, Noryl Chamber, Plastic Thrust Roller, Bronze Bottom, Meter Mounted Low Temp Register, No Connections, NSF 61, Cubic Feet Reader  
 COIL BOX - Mueller No. 330 CS 18 36 LSBUN  
 LID - Mueller No. 790018  
 INSULATION RING - Mueller No. 790153



TITLE		
WATER SERVICE CUSTOMER H/U W/ SCVA BACKFLOW STANDARD DOMESTIC DETAIL		
SHEET	1 OF 5ET	DWG SCALE NO SCALE
DRAWN BY: RJA		